

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. Sec. R. <u>33</u> E. W.	F3 & G2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner F3:	Wood post (Not found. No subsequent monuments found.)	
	Y. Pine 22 N28E 7 (Found. No subsequent accessories found.)	
	W. Pine 16 S51W 40 ( " " " " " " )	
Corner G2:	Wood post (Not found. No subsequent monuments found.)	
	Y. Birch 6 N33E 27 ( " " " " accessories " )	
	Sugar 16 S57W 32 ( " " " " " " )	

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner F3: Corner replaced 6/27/74 from stumps of original BT's, found by measuring from original corners 2½ miles W and ½ mile E. Stumps are burned and have no marks, but agree with original record as to species, absolute and relative size, distance, and bearing.

Corner G2: Re-established 7/8/74 proportionately on line between original Sec. Corners 39.880 ch. S and 41.053 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner F3: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Red Pine Stump N29½°W (mag.) 37.0 ft. "NBT"  
 Red Pine Stump N29° E (mag.) 4.3 ft. "NBT"  
 Red Pine Stump S54° E (mag.) 35.0 ft. "NBT"

Corner G2: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Sugar Maple 6 N87°E (mag.) 11.5 ft. "1/4S, NBT"  
 Sugar Maple 7 S33°W (mag.) 5.0 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE September 24, 1975  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

