

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                       | LOCATED IN--                                     | CORNER CODE NUMBER |   |
|--|--|--------------------|---|
| 1. PUBLIC LAND SURVEY                  | T. <u>43</u> N. S. R. <u>33</u> E. W.            | D5                 | REGISTER OF DEEDS STAMP AND FILING NUMBER |
| 2. PROPERTY CONTROLLING IN SECTION     | <u>8</u> , T. <u>43</u> N. S. R. <u>33</u> E. W. | 15 & 16            |   |
| 3. MISCELLANEOUS PROPERTY IN SECTION   | , T. _____ N. S. R. _____ E. W.                  |                    |   |
| 4. LOT NO. _____ , RECORDED PLAT _____ |  |                    |   |
| 5. PRIVATE CLAIMS _____                |  |                    |   |

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 20, 1974 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner D5: Wood post (Not found. No subsequent monuments found.)  
 Y. Birch 6 S21E 3 ( " " " " accessories " )  
 Cedar 6 N89E 27 ( " " " " " " )

Corners 15 & 16: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner D5: Re-established on line between Sec. Cor. 39.994 ch. to E and to W. Found a recent 2"x2"x6' squared forester's picket S25°E 20.9 ft. for an approximate corner.  
 Corner 15: Established on line between Sec. Cor. 19.997 ch. W and 1/4 cor. 19.997 ch. E.  
 Corner 16: Established on line between Sec. Cor. 19.997 ch. E and 1/4 cor. 19.997 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Witnesses for Corner D5: B. Spruce 6 N85°W (mag.) 6.8 ft. "1/4S, NBT"  
 B. Spruce 5 N77°E (mag.) 38.0 ft. "1/4S, NBT"  
 Witnesses for Corner 15: W. Spruce 18 N 8°E (mag.) 23.9 ft. "1/16S, BT"  
 W. Spruce 14 S30°E (mag.) 8.7 ft. "1/16S, BT"  
 Note: Distances horizontal.  
 Witnesses for Corner 16: B. Spruce 5 S51°W (mag.) 21.3 ft. "1/16S, BT"  
 B. Spruce 10 East (mag.) 18.5 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE September 24, 1975  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

