

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 43 ^{N.} S. R. 33 ^{XX} W.	C7
2. PROPERTY CONTROLLING IN SECTION 18 _____	T. 43 ^{N.} S. R. 33 ^{XX} W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C7: Wood post (Not found. No subsequent monuments found.)
 W. Pine 28 N82W 29 (" " " " accessories ")
 W. Pine 16 S65E 29 (" " " " " ")

Corner 14: Not established in original survey. Apparently established approximately, in this century; found a squared fence post (all others round) in an E & W fence line, S44°W 12.9 ft. from corner reported here.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C7: On 7/12/74, re-established corner in line of an E & W farm fence where it intersects the paving centerline of a N & S county road, each feature purported by common report, and accepted locally, as being on the section lines of at this point. Sec. Cor. 5, 6, 31, & 32 on N twp. boundary is N0°07'30"W 240.74 ch. from this corner, the record being N0°31'W 240.83 ch.; and Sec. Cor. 13, 18, 19, & 24 on W twp. boundary is N89°47'W 80.36 ch., the record being N89°37'W 80.67 ch. By actual measurement of the lines, all E & W distances between corners in the 4 miles going E from 13, 18, 19, & 24 were found to be short of the original record.

Corner 14: Established 10/21/74 on line between Sec. Cor. 20.091 ch. S and 1/4 cor. (in

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C7: 9/16" x 12" Copperweld pin in road.
 Power Pole S49½°W 28.06 ft.
 Telephone Pole N34½°W 43.83 ft.
 Distances are to nail with 3/4" brass washer stamped "REF. MARKER".

Cedar 14: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Cedar 20 S40°W (mag.) 46.6 ft. "1/16S, BT"
 Cedar 18 N42°W (mag.) 56.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

