

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> XX N. R. <u>33</u> XX W.	C1
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. _____ N. R. <u>33</u> XX W.	7 & 7a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C1: Cedar post (Not found. No subsequent monuments found.)
 W. Pine 7 N77E 36 (" " " " accessories ")
 Elm 10 N67½W 87 (" " " " " ")
 Corner 7: Not established in original survey nor subsequently, apparently.
 Corner 7a: Wood meander post (Not found. No subsequent monuments found.)
 Spruce 6 S20E 90 (" " " " accessories ")
 Maple 10 N57W 30 (" " " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C1: Re-established 7/24/74 on line between original 1/4 cor. 39.911 ch. W and original sec. corner 79.821 ch. E. Distance W to river is now 1.57 ch. and S to river is now 2.00 ch. Original distances were 1.32 ch. and 1.00 ch., respectively.
 Corner 7: Established 7/10/74 proportionately on line between 1/4 cor. 20.076 ch. S and Sec. Cor. 20.027 ch. N.
 Corner 7a: Re-established 7/10/74 (but probably not in original position) on true sec. line on S bank of Paint River, 10.747 ch. S of Sec. Cor. 5, 6, 31, & 32. The record distance is given as 9.82 ch., but the river at this point is a large bend, has a rapid current, and is the kind of situation where accretions on the N bank and relictions on the S bank are likely to occur. Distance

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

across river on sec. line is 8.75 ch., record distance was 9.82 ch., which checks closely.
 Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Witnesses for Corner C1: Red Maple 6 S28°W (mag.) 26.9 ft. "S 6, NBT"
 Elm 7 N62°W (mag.) 5.8 ft. "S31, NBT"
 Witnesses for Corner 7: Red Maple 5 S46°W (mag.) 16.2 ft. "1/16S, BT"
 B. Spruce 6 S50°E (mag.) 4.0 ft. "1/16S, BT"
 Witnesses for Corner 7a: Silver Maple 6 S61°E (mag.) 13.4 ft. "M.C., NBT"
 B. Ash 8 S15°W (mag.) 47.4 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 7, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

