

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> ^{N.} S. R. <u>33</u> ^{E.} W.	E1 & E2
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>43</u> ^{N.} S. R. <u>33</u> ^{E.} W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E1: Spruce post	(Not found. No subsequent monuments found.)	
W. Pine 32 N21E 46	(Found. " " accessories ")	
W. Pine 24 S39W 30	(" " " " " ")	
W. Pine 20 S85E 46	(" " " " " ")	
Hemlock 14 N24W 21	(Not found. " " " " ")	
Corner E2: Wood post	(Not found. " " monuments found.)	
Fir 12 S61E 20	(" " " " accessories ")	
Fir 10 N32W 4	(" " " " " ")	

Corner 3: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E1: Corner replaced 7/11/74 from stumps of three BT's noted above, identified by species and relative positions and by measurements from original corners 1½ miles W and 1 mile E, and confirmed by the remains of a down W. Pine line tree in proper position 3.92 ch. N.

Corner E2: Re-established 6/27/74 proportionately on line between Sec. Cor. 40.228 ch. S and Sec. Cor. 40.809 ch. N.

Corner 3: Established proportionately on line between 1/4 cor. 20.114 ch. S and Sec. Cor. 20.695 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.

Witnesses for Corner E1:	W. Pine 20 N55°E (mag.) 39.2 ft. "S33, NBT"
	W. Spruce 7 S46½°E (mag.) 49.4 ft. "S4, NBT"
	W. Birch 14 N43°W (mag.) 17.7 ft. "S32, NBT"
Witnesses for Corner E2:	W. Pine 24 S19°W (mag.) 37.6 ft. "1/4S, NBT"
	W. Pine 24 S20°E (mag.) 52.2 ft. "1/4S, NBT"
Witnesses for Corner 3:	W. Pine 22 S84°E (mag.) 77.1 ft. "1/16S, BT"
	W. Pine 20 N89°W (mag.) 129.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 17, 1975

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

