

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION _____ 8 _____, T. _____ 43 _____	N. _____ XX R. _____ 33 _____ W. _____	7a, 14, & 14a
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 26 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners 7a & 14a: Meander corners on N and S banks of Chicaugon Creek. Posts and witnesses established in original survey, but could find no evidence of either the original posts or their accessories or of any replacement monuments or accessories.

Corner 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 7a: Re-established proportionately on line between Sec. Cor. 40.898 ch. S and 39.556 ch. N. Note: 1/4 cor. falls in creek on sec. line 44.3 ft. S of this corner.

Corner 14: Established on line between Sec. Cor. 20.113 ch. S and 1/4 cor. (in creek) 20.114 ch. N.

Corner 14a: Re-established proportionately on sec. line on S bank of creek, 39.296 ch. N of Sec. Cor. to S and 41.158 ch. S of Sec. Cor. to N.
Note: 1/4 cor. falls in creek on sec. line 61.5 ft. N. of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Witnesses for Corner 7a: W. Spruce 14 N74°W (mag.) 52.9 ft. "M.C., NBT"
Balsam 8 (on NW side of large boulder) S71°E (mag.) 22.4 ft. "M.C., NBT"

Witnesses for Corner 14: W. Spruce 10 N77°E (mag.) 11.8 ft. "1/16S, BT"
W. Spruce 12 N78 1/2°W (mag.) 24.0 ft. "1/16S, BT"

Witnesses for Corner 14a: Tamarack 12 S22°W (mag.) 114.0 ft. "M.C., NBT"
W. Spruce 12 S39°E (mag.) 103.4 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 17, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

