

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> <sup>N.</sup> <del>S.</del> R. <u>33</u> <sup>W.</sup> <del>E.</del>	C2 & C3
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>43</u> <sup>N.</sup> <del>S.</del> R. <u>33</u> <sup>W.</sup> <del>E.</del>	14 & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <del>S.</del> R. _____ <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner C2: Wood post (Not found. No subsequent monuments found.)
  - Spruce 10 S49W 20 ( " " " " accessories " )
  - Fir 12 N30E 9 ( " " " " " " )
- Corner C3: Wood post (Not found. No subsequent monuments found.)
  - Cedar 10 N72E 8 ( " " " " accessories " )
  - Cedar 10 S72W 7 ( " " " " " " )
- Corners 14 & 16: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner C2: Re-established 12/21/73 on line between Sec. Cor. 40.152 ch. S and 40.103 ch. N. Found a 10" aspen blazed on 4 sides N72½°W 2.485 ch., from which a foresters' paint line runs S. It seems obvious on the basis of measurements to other corners that the blazed tree was only a guess as to corner location.
- Corner C3: Re-established 12/17/73 by double proportionate measurement from original corners 1 mile W and 1½ miles E and re-established corners 1 mile N and 2 miles S.
- Corner 14: Established 7/12/74 on line between Sec. Cor. 20.076 ch. S and 1/4 cor. 20.076 ch. N.
- Corner 16: Established 7/12/74 on line between Sec. Cor. 20.009 ch. E and 1/4 cor. 20.009 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monuments for C2 & C3: 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Monuments for 14 & 16: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
- Witnesses for Corner C2: W. Spruce 20 S86°W (mag.) 38.7 ft. "1/4S, NBT"  
Balsam 11 N47°W (mag.) 29.7 ft. "1/4S, NBT"
- Witnesses for Corner C3: B. Spruce 6 N13½°W (mag.) 31.4 ft. "S6, NBT"  
Balsam 6 S60½°W (mag.) 8.3 ft. "S7, NBT"  
Elm 6 S20°E (mag.) 24.3 ft. "S8, NBT"
- Witnesses for Corner 14: Balsam 6 S35°W (mag.) 7.5 ft. "1/16S, BT"  
Cedar 9 N46½°W (mag.) 40.1 ft. "1/16S, BT"
- Witnesses for Corner 16: Sugar Maple 13 N46°E (mag.) 4.2 ft. "1/16S, BT"  
Y. Birch 6 N71°W (mag.) 2.7 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE October 20, 1975

*Arthur O. Enger*  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

