

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> ^{N.} S. R. <u>33</u> ^{W.} E.	B7
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	, T. <u>43</u> ^{N.} S. R. <u>33</u> ^{W.} E.	16
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 28 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B7: Wood post (Not found. L.E.S. control post S74E 53.8 ft.)
 Y. Birch 18 N45W 40 (" " No subsequent accessories found.)
 Sugar 8 S60E 18 (" " " " " ")

Corner 16: Not established in original survey. Found a 1" I.D. iron pipe in a N & S fence line S19°E 39.5 ft. from corner reported here.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B7: L.E.S. control posts were established in the 1930's to guide Land Economic Survey personnel in their work, and little effort was made to place them at the original corner positions. This one is not consistent with other corner evidence to E & W, therefore was not accepted by the undersigned. Re-established the corner proportionately on line between Sec. Cor. 40.165 ch. E and 40.195 ch. W.

Corner 16: The found pipe was probably set from the L. E. S. post and therefore is not considered by the undersigned to be in the proper place. Re-established the corner on line between Sec. Cor. 20.083 ch. E and 1/4 cor. 20.083 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B7: 1" I.D. x 36" iron pipe with 3½" aluminum cap
 Sugar Maple 8 N78°E (mag.) 5.0 ft. "1/4S, NBT"
 Sugar Maple 7 S53°W (mag.) 13.5 ft. "1/4S, NBT"
 Corner 16: 1" I.D. x 36" iron pipe with 3½" aluminum cap
 Sugar Maple 6 S33°W (mag.) 34.7 ft. "1/16S, BT"
 Sugar Maple 6 N79°W (mag.) 11.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20, 1975

Michigan Department of Natural Resources
 Arthur O. Enger

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

