

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 ^{N.} 38 , R. 33 ^{W.} 33	D1
2. PROPERTY CONTROLLING IN SECTION_____	5, T. 43 ^{N.} 38 , R. 33 ^{W.} 33	1a & 2
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____, R. _____, S. _____, E. _____, W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D1:	Cedar post	(Not found. No subsequent monuments found.)
	Hemlock 20 N38E 15	(" " " " accessories ")
	Hemlock 14 N56W 17	(" " " " " ")
Corner 1a:	Wood meander post	(Not found. No subsequent monuments found.)
	Maple 10 S53W 21	(" " " " accessories ")
	Fir 7 N10E 53	(" " " " " ")

Corner 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D1: Re-established 7/11/74 on line between Sec. Cor. 39.911 ch. to E and to W.

Corner 1a: Re-established 7/24/74 on true sec. line on W bank of Paint River, 20.262 ch. E of Sec. Cor. and 19.649 ch. W of 1/4 cor.

Corner 2: Established 7/11/74 on line between Sec. Cor. 19.955 ch. E and 1/4 cor. 19.955 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.

Witnesses for Corner D1: Sugar Maple 12 S25°W (mag.) 11.2 ft. "1/4S, NBT"
 Red Maple 12 N41°W (mag.) 13.3 ft. "1/4S, NBT"

Witnesses for Corner 1a: Silver Maple 14 S44°W (mag.) 70.3 ft. "M.C., NBT"
 White Pine 24 N68°W (mag.) 50.8 ft. "M.C., NBT"

Note: Distances horizontal

Witnesses for Corner 2: W. Birch 6 N44°W (mag.) 10.6 ft. "1/16S, BT"
 Balsam 4 S83°E (mag.) 28.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 20, 1975

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

