

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION _____ 18 _____, T. _____ 43 _____	XX S., R. XX 33 _____ XX E. W.	2 & 7
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Neither corner established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 2: Established 6/19/74 on line between Sec. Cor. 19.991 ch. E and 1/4 corner 19.991 ch. W.
- Corner 7: Established 10/21/74 on line between 1/4 cor. (in pond) 20.039 ch. S and Sec. Cor. 20.039 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 2: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
Sugar Maple 10 S14°E (mag.) 3.2 ft. "1/16S, BT"
Sugar Maple 9 N56°W (mag.) 10.4 ft. "1/16S, BT"
- Corner 7: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
Sugar Maple 4 N77°W (mag.) 3.3 ft. "1/16S, BT"
Sugar Maple 4 N18°E (mag.) 11.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 22, 1975

CHIEF OF SURVEY PARTY

 Michigan Registered Land Surveyor
 Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

