

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>43</u> <sup>N.</sup> <del>S.</del> R. <u>33</u> <sup>W.</sup> <del>E.</del>	C5	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>7</u>	T. <u>43</u> <sup>N.</sup> <del>S.</del> R. <u>33</u> <sup>W.</sup> <del>E.</del>	14	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <del>S.</del> R. _____ <sup>E.</sup> <del>W.</del>	_____	
4. LOT NO. _____, RECORDED PLAT _____		_____	
5. PRIVATE CLAIMS _____		_____	

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner C5: Wood Post (Not found. No subsequent monuments found.)  
           Hemlock 22 N77W44 ( " " " " accessories " )  
           Sugar 14 S35E41 ( " " " " " " )  
 Corner 14: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner C5: Re-established 6/18/74 by proportionate measurement on true line between Sec. Cor. 80.241 ch. S and 80.242 ch. N, in accordance with method used in original survey. The record distance between each of these corners is 80.273 ch. Found this position also to be in agreement, within 4 links, with an original section corner 80.162 ch. W, the original record distance being 80.20 ch.

Corner 14: Established 6/19/74 on line between Sec. Cor. 20.060 ch. S and 1/4 cor. 20.061 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner C5: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
           Sugar Maple 18 S75°E (mag.) 14.7 ft. "S17, NBT"  
           Sugar Maple 10 S35°W (mag.) 36.6 ft. "S18, NBT"  
           Basswood 10 N31°W (mag.) 13.7 ft. "S 7, NBT"  
 Corner 14: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
           Sugar Maple 5 N56°E (mag.) 15.3 ft. "1/16S, BT"  
           Sugar Maple 5 S83°W (mag.) 3.8 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 22, 1975  
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

