

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. <u>2</u> , R. <u>33</u> E. <u>W.</u>	C6
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on October 21, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner falls in pond and was never established. A Witness Corner for it was established in the original government survey, 1.00 ch. S of true corner, marked with a wood post and itself witnessed with a Tamarack 12 S15W 27, the stump of which was found, and a Cedar 8 S56E 13, not found. A 2"x2"x4' squared cedar post had been set as a subsequent W. C., but at a point N22°E .167 ch. from the tamarack BT.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Placed a monument at original W. C. position from the tamarack BT, identified from part of axe notch on the witness blaze. Corner falls on S margin of pond, true 1/4 cor. is in pond 1.00 ch. N. Note: This corner is not alined with section corners 39.181 ch. S and 41.077 ch. N, as reported in original field notes; it appears to have been corrected in the wrong direction from the original random line, or not corrected at all. The original subdividing surveyor was accused of doing things like that by an examining deputy surveyor, as reported in original notes for T45N, R34W.

Also established a second Witness Corner on the E & W 1/4 line of Sec. 17, on east margin of pond. True 1/4 cor. is on extension of 1/4 line, N89°05'W 2.673 ch. from this W.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both witness corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.

Witnesses for original W.C.: Cedar 6 S 40°W (mag.) 33.3 ft. "W.C., NBT"
 Cedar 5 S44°E (mag.) 21.3 ft. "W.C., NBT"
 Witnesses for second W.C.: Twin Cedar 5 N79°E (mag.) 12.4 ft. "W.C., NBT"
 Twin Cedar 5 S39°E (mag.) 16.3 ft. "W.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

