

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. 43 N. & R. 33 E. W.	E5	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION 16_____	, T. 43 N. & R. 33 E. W.	1 & 3	
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. & R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner E5: Wood post	(Not found. No subsequent monuments found)
Hemlock 20 N47W 72	( " " " " accessories " )
Y. Birch 10 S47E 53	( " " " " " " )

Corners 1 & 3: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner E5: Re-established 5/7/74 proportionately on line between North M.C. bet. Sec. 16 & 17 and calculated position of 1/4 cor. bet. Sec. 8 & 9, computed to be in line between the first above-named corner and Sec. Cor. 4, 5, 8, & 9 and falling in Chicaugon Creek, according to the original survey notes. Found this position to be most in agreement with the original notes to the foot of a hill 1.50 ch. E, but there are a number of confusing calls in the notes which it is difficult to reconcile.

Corner 1: Established 7/2/74 on line between Sec. Cor. 19.768 ch. W and 1/4 cor. 19.767 ch. E. Corner is in open marsh about 3 1/2 ch. E of marsh edge to W.

Corner 3: Established 5/7/74 on line between Sec. Cor. 20.252 ch. N and 1/4 cor. 20.252 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner E5:	1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
	W. Pine 15 S29°W (mag.) 57.9 ft. "S17, NBT"
	W. Pine 16 S25°E (mag.) 41.0 ft. "S16, NBT"
Corner 1:	1" I.D. x 42" iron pipe with 3 1/2" aluminum cap.
	Tamarack 1 S58°E (mag.) 48.5 ft. "1/16S, BT"
	Tamarack 2 S69°W (mag.) 74.3 ft. "1/16S, BT"
Corner 3:	1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
	Red Pine 6 N19°E (mag.) 44.8 ft. "1/16S, BT"
	Red Pine 7 S53°E (mag.) 34.7 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1975

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

