

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                            | LOCATED IN--:   | CORNER CODE NUMBER   |
|--|---|----------------------|
| 1. PUBLIC LAND SURVEY _____                  | T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>33</u> <sup>E.</sup> / <sub>W.</sub> | <u>E6</u>            |
| 2. PROPERTY CONTROLLING IN SECTION <u>16</u> | T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>33</u> <sup>E.</sup> / <sub>W.</sub> | <u>10a &amp; 10b</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____   | T. _____ <sup>N.</sup> / <sub>S.</sub> R. _____ <sup>E.</sup> / <sub>W.</sub>         | _____                |
| 4. LOT NO. _____, RECORDED PLAT _____        |   |                      |
| 5. PRIVATE CLAIMS _____                      |   |                      |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19    , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19    , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner E6: Wood post (Not found. No subsequent monuments found.)
    - Hemlock 16 N58W 42 ( " " " " accessories " )
    - Cedar 12 S71E 14 ( " " " " " " )
  - Corner 10a: Wood meander post (Not found. No subsequent monuments found.)
    - W. Pine 10 N54W 56 (Probably found.)
    - Y. Pine 10 N67E 46 ( " " " )
  - Corner 10b: Wood meander post (Not found. Found 1½" I.D.x44" iron pipe in place.)
    - Y. Pine 10 S58E 22 (Probably found.)
    - Y. Pine 12 S 4W 22 ( " " " )

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**  
 Corner E6: Re-established 5/7/74 proportionately on line between M.C. 5.142 ch. S and Sec. Cor. 40.503 ch. N.

Corner 10a: Re-established 5/7/74 from stumps of two probable BT's noted above, identified by species, relative size, distance and bearing. M.C. position as determined from them agrees explicitly with original meander notes going CCW around lake from this point, calling for a course N73W 2.50 ch. and on which at .75 ch. a marsh was entered and at 2.50 ch. was left.

Corner 10b: On 11/16/72 replaced found monument with monument described below. Monument placed from two probable BT's noted above, by unknown parties. BT stumps agree with originals in species, relative size, distance, and bearing; slab with old axe notch found on SE BT.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Corner E6: 3½" O.D. x 42" concrete-filled iron pipe with brass cap.
    - Red Maple 5 N50°E (mag.) 22.1 ft. "1/4S, NBT"
    - W. Birch 10 N47°W (mag.) 27.3 ft. "1/4S, NBT"
  - Corner 10a: 3½" aluminum cap with ½" x 12" re-rod, embedded in poured concrete
    - Red Pine 11 N21°W (mag.) 20.05 ft.) Distances to nail with 3/4" brass
    - Red Maple 6 N75°W (mag.) 32.98 ft.) washer, stamped "WITNESS MARK"
  - Corner 10b: 1" I.D. x 36" iron pipe with 4" aluminum cap.
    - Red Pine 10 S26°W (mag.) 24.76 ft. ) Distances to nail with 3/4" brass
    - Red Pine 20 S77½°E (mag.) 44.90 ft.) washer, stamped "REF MARKER"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1975  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

