

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. <del>XX</del> R. <u>33</u> <del>XX</del> W.	<u>G 1 &amp; H 1</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 19 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner G1:** Sugar post (Not found)  
 Sugar 12 N18E 13 " "  
 Sugar 12 N70W 15 (Found)  
 Sugar 14 S49E 22 (Not found)  
 Sugar 12 S40W 43 " "

Found an 8" sugar maple blazed on 4 sides N15 $\frac{1}{2}$ °W 5.1 ft.

**Corner H1:** Ironwood post (Not found)  
 Y. Birch 8 N25W 4 (Not found)  
 Y. Birch 16 N 5E 32 (Found)

Found an old 4"x4"x5 $\frac{1}{2}$ ' squared cedar post in place.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner G1:** Re-monumented from rotted remains of original BT indicated above, identified from overgrowth and axe marks for upper and lower faces. Position recovered by measurements from original corners 79.726 ch. W and 79.686 ch. E.

**Corner H1:** Re-monumented from rotted remains of original BT indicated above, identified from traces of overgrowth on an old blazed face. Wood post had been set at record bearing and distance from BT. Position confirmed by measurements from original section corners 39.834 ch. W and 39.852 ch. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner G1:** 1" I.D. x 42" iron pipe with 3 $\frac{1}{2}$ " aluminum cap.  
 Sugar Maple 8 N15 $\frac{1}{2}$ °W (mag.) 5.1 ft. "S33, NBT"  
 Sugar Maple 6 S72° E (mag.) 19.9 ft. "S 3, NBT"  
 Hemlock 16 S30° W (mag.) 44.3 ft. "S 4, NBT"

Also blazed and scribed a 7" Sugar Maple S78°W 1.7 ft. from corner (from center of tree)

**Corner H1:** 1" I.D. x 39" iron pipe with 3 $\frac{1}{2}$ " aluminum cap.  
 Sugar Maple 13 N35°W (mag.) 21.3 ft. "1/4S, NBT"  
 Elm 10 S42°E (mag.) 10.1 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE February 27, 1974

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

