

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>43</u> N. XX R. <u>33</u> XX W.		<u>A6 & A7</u>
2. PROPERTY CONTROLLING IN SECTION <u>18</u> T. <u>43</u> N. S. R. <u>33</u> XX W.		<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A6: Cedar post (Not found. No subsequent monuments found)
 Cedar 6 S28E 13 (Not found. No subsequent accessories found)
 Cedar 8 N49W 15 (" " " " " ")

Corner A7: Sugar post
 Sugar 16 S29E 37 Hemlock 32 N68W 13
 Sugar 14 N14E 14 Hemlock 24 S33W 12

Original post or accessories not found. Found a 1½" I.D. x 36" iron pipe in place, which purports to be the named corner. Pipe possibly placed by E. Davison, former County Road Engineer.
Corner 10: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A6: Re-established 11/8/72 proportionately on line between Sec. Corners 40.145 ch. to N and to S. Distance S to river edge agrees substantially with original field notes.
Corner A7: Corner accepted as found, as it is consistent with original evidence found on township line north of it. Notes of G. A. Shadko, R.L.S., indicate that this monument may have been placed by measurement from a corner a mile to the West; if so, it arrived at an acceptable point, even though the proper procedure was not followed. No other record evidence of the monument's origin was found.
Corner 10: Established 11/9/72 on line between Sec. Corner 20.072 ch. S and 1/4 corner 20.072 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A6: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 (Variation 1°00' West) Cedar 16 S75°W (mag.) 15.3 ft. "1/4S, NBT"
 Cedar 6 S18°E (mag.) 5.0 ft. "1/4S, NBT"
 Cedar 8 N 8°E (mag.) 5.0 ft. "1/4S, NBT"
Corner A7: 5" x 36" re-inforced concrete cylinder with 4" aluminum cap.
 W. Birch 12 N73°E (mag.) 10.31 ft.
 Sugar Maple 7 S56°E (mag.) 21.00 ft.
 Sugar Maple 7 N87°W (mag.) 42.81 ft.

Distances are to a nail with 3/4" brass washer stamped "REF. MARKER" on root collar of above trees.

Corner 10: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Cedar 6 N56°W (mag.) 20.4 ft. "1/16S, BT" Cedar 5 S50°W (mag.) 10.8 ft. "1/16S, BT.
 Also squared and scribed a 5" B. Spruce S10°W 1.0 ft. from corner.

SIGNED BY _____ DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE February 27, 1974

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

