

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. XX R. <u>33</u> XX W.	A8
2. PROPERTY CONTROLL- 19 ING IN SECTION_____	, T. <u>43</u> N. XX R. <u>33</u> E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A8: Sugar post (Not found)
 Sugar 16 S29E 37 (Not found - No subsequent accessories found.)
 Hemlock 32 N68W 13 " " " " " " " "

Found an old drill rod surrounded by three blazed trees labelled "BT", S88½°E .714 ch. from corner reported herein.

Corner 3: Not established in original survey nor subsequently apparently--at least, I could find no physical or record evidence of a corner in the reasonable vicinity of the corner reported herein.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A8: Re-established 11/9/72 on line between Sec. Corners 40.091 ch. to N and to S. The found drill rod appears to have been intended to be set midway on line between a sec. cor. monument to N and one to the S; as evidence indicates the latter to be erroneously placed, the monument found at this corner was also rejected, for the reason that it is dependent on the erroneous monument.

Corner 3: Established 11/6/72 on line between Sec. Corner 20.045 ch. N and 1/4 corner 20.045 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner A8: Sugar Maple 7 S 1°W (mag.) 8.0 ft. "1/4S, NBT"
 Sugar Maple 7 N35°W (mag.) 5.4 ft. "1/4S, NBT"
 Sugar Maple 6 N50°E (mag.) 20.2 ft. "1/4S, NBT"

Witnesses for Corner 3: Sugar Maple 4 S72°E (mag.) 13.0 ft. "1/16S, BT"
(Variation 0°50' East) W. Birch 6 N16°W (mag.) 12.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 27, 1974

CHIEF OF SURVEY PARTY
Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

