

SURVEY & REMONUMENTATION

JAN 12 1996

COMMISSION

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 15 PM 2:21
LC Records 26 P 405
Gary L. Pisoni
REGISTER OF DEEDS

For corners in

Iron
(County)

Located in:

Corner Code =#

- | | | | |
|------------------------------------|-------------------------|--------------------|------------|
| 1. Public Land Survey | | <u>T 43N R 34W</u> | <u>A-2</u> |
| | | T 43N R 35W | M-2 |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 1 & 6 T43N, R35-34W

I, Gary L. Pisoni, in a field survey on October 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor in 1846.
Original corner: Cedar Post
Original bearing trees:
White Pine 6" S 66° E 13 links (8.58 feet)
Cedar 5" N 78° W 14 links (9.24 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Corner restored by single proportionate measurement methods on line between the Northwest corner of Section 6, T43N R34W and the West Quarter corner of Section 7, T43N R34W.
Quarter corner is 28.5 feet South of a old East-West fence line.

Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, R34W, 1/4, S-1, S-6, 1995, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Black Spruce	10"	N 49° E	26.77 feet
Red Maple	8"	S 76° E	32.42 feet
Black Spruce	6"	S 46° W	26.17 feet
Black Spruce	12"	N 76° W	44.09 feet
Steel Sign Post		North	0.71 feet

PEER GROUP APPROVED

Gary L. Pisoni 12-14-95

COUNTY REPRESENTATIVE

Signed by Gary L. Pisoni

Date 11-30-95

Surveyor's Michigan License No. 27457

