

RECORDED

MAR 10 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>M-11</u>
	T <u>43N</u> R <u>34W</u>	<u>A-11</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:33

L.C. Records: L.8, P. 130

*Gary L. Pisoni*  
REGISTERED SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner to Sections 25 and 36, T43N, R35W  
Section Corner to Sections 30 and 31, T43N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 11, 1846 by William A. Burt, U.S. Deputy Surveyor.

Original Corner; Fir Post

Original Bearing Trees:

Sugar	14"	N 71 °E	38 lks (25.08 feet)
Yellow Birch	20"	S 29 °W	20 lks (13.20 feet)

PEER GROUP APPROVED

*Gary L. Pisoni*  
COUNTY REPRESENTATIVE

In 1978, Gary L. Pisoni, RLS, found an iron pipe located in the centerline of Kofmehl Road which runs East and West marking the corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Iron pipe has been used for many surveys in the surrounding area. In recent years, a new layer of asphalt has been laid over the top of the existing pipe. Set a P.K. nail over the top of existing pipe. I accept the pipe as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set one (1) reference monument, being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R35W, R34W, R.M., S-25, S-30, S-36, S-31, South, 30.11 feet, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Fire Hydrant		N 28°W	31.55 feet
R.M.	5/8" x 30" rebar	North	30.11 feet
Utility Pole	M87-2	S 62° E	62.48 feet
Utility Pole	M87-1	S 66° W	75.01 feet
Steel sign post		North	30.96 feet

99-130

Signed by *Gary L. Pisoni*

Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

