

**SURVEY &
REMONUMENTATION**

JAN 12 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 DEC 15 PM 2:21

LC Records LG, P409

Gilbert Stebbins
REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 43NR 34W	B-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner 6 & 7 T43N R34W

I, Gary L. Pisoni, in a field survey on Oct. 20, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3	•											
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Guy H. Carleton, U.S. Deputy Surveyor in 1851.
Original corner: Wood Post
Original bearing trees:
Sugar 14" S 69° E 26 links (17.16 feet)
Yellow Birch 20" N 72° E 19 links (12.54 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Found a 4"x4" concrete monument located at a fence corner and set by Donald D. Lappala RLS in the middle 1970's and recorded in Liber 2, of L.C. Records, Page 45. GLO distance between section corners checks good. I accept the concrete monument as the best available evidence for restoring the corner position.

Replaced concrete monument with aluminum pipe monument as described below.

ACT 74 Research on file with County Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner COUNTY REPRESENTATIVE

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R34W, S-6, 1/4, S-7, 1995, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple (Exist)	10"	N 21° E	29.52 feet
Sugar Maple "	16"	S 77° E	12.33 feet
Sugar Maple "	9"	S 65° W	14.06 feet
Sugar Maple "	7"	N 71° W	22.11 feet
Steel Sign Post		South	0.87 feet

PEER GROUP APPROVED
Gary L. Pisoni 12-14-95
IRON COUNTY REPRESENTATIVE

Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 11-30-95

