

# SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

97 DEC 23 PM 1:29  
*L.L. Records L.P. 157*

*Gary L. Pisoni*  
REGISTER OF DEEDS

For corners in

Iron		Located In:	
(County)			Corner Code #
1. Public Land Survey		T <u>43N</u> R <u>34W</u>	<u>B-7</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 18 and 19, T43N, R34W

I, Gary L. Pisoni, in a field survey on November 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post				
Original Bearing Trees;	Lynn	12"	S15° E	23 lks.(15.18 feet)
	Yellow Birch	12"	N20° W	27 lks.(17.82 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original corner evidence was recovered.

Found corner marked by a 3/4" diameter bolt, 12 inches long, located in the Center-Line of an un-improved road running North and South and on a fence line running East and West. I accept the bolt as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

In place of iron bolt, set a 5/8 inch diameter rebar, 30 inches long, with a 3 inch diameter aluminum cap, 6 inches below the roadbed surface. Cap is stamped as follows; Iron County Remonumentation, T43N, R34W, 1/4, S18, S19, 1997, RLS 27457. Blazed and scribed the following new bearing trees;(Measurements taken to a nail in side of tree)

Basswood	11"	N 17° E	49.28 feet
Basswood	13"	S 46° E	15.05 feet
Elm	7"	N 71° W	25.71 feet
Sugar Maple	12"	N 34° W	26.72 feet
Steel sign post		West	15.85 feet

**PEER GROUP APPROVED**  
*Gary L. Pisoni 12-1-97*  
IRON COUNTY REPRESENTATIVE

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

97-52  
Signed by *Gary L. Pisoni*  
Surveyor's Michigan License No. 27457

Date November 29, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1971  
REVISED MAY 19, 1975  
REVISED JAN. 1983  
REVISED OCT. 1995

