

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY MICHIGAN  
RECEIVED FOR RECORD  
97 DEC 23 PM 1:29  
L.C. Records L.7 P. 156  
*Eileen Steed*  
REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>34W</u>	<u>C-8</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 19 and 20, T43N, R34W

I, Gary L. Pisoni, in a field survey on November 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post			
Original Bearing Trees;	Sugar	8"	N51° E
	Yellow Birch	18"	S39° W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence was recovered.

Corner position found marked by a 3" x 36" long light guage railroad rail at the intersection of a 4-way fence line. Distance along section line is very close to GLO distance. This position has been used as the corner for 60 years plus and there were many surveys tied to this position. I accept the railroad rail as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

In place of railroad rail, set a 2 inch diameter aluminum pipe monument, 30 inches long, 3 inches above the ground surface, with a 3 inch diameter aluminum cap stamped as follows; Iron County Remonumentation, T43N, R34W, 1/4, S19, S20, 1997, RLS 27457. Blazed and scribed the following new bearing trees; (Measurements are taken to a nail in side of tree)

Black Cherry	8"	N15° E	14.60 feet
Red Maple	7"	N66° E	23.96 feet
Red Maple	4"	S14° W	24.48 feet
Red Maple(DBL)	4"	S67° W	43.98 feet
Steel Sign Post		N41° W	0.85 feet

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19	●	20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PEER GROUP APPROVED  
*Gary L. Pisoni 12-1-97*  
IRON COUNTY REPRESENTATIVE

39 lks.(25.74 feet)  
44 lks.(29.04 feet)

97-51  
Signed by Gary L. Pisoni  
Surveyor's Michigan License No. 27457

Date November 29, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
STATE OF MICHIGAN  
GARY L. PISONI  
REGISTERED LAND SURVEYOR  
No. 27457  
RECEIVED MAY 14 1997  
REVISED JAN. 1993  
REVISED OCT. 1985