

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T.43N R.34W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD**

98 DEC 28 AM 11:11

L.C. Records: L. 7, P. 239

Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 29, 30, 31, 32, T43N, R34W

I, Gary L. Pisoni, in a field survey on October 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Sugar	10"	N 35°W	42 lks (27.72 feet)
Yellow Birch	10"	S 30°E	16 lks (10.56 feet)

PEER GROUP APPROVED

Gary L. Pisoni 11-24-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a light gauge steel rail marking the corner position and in line with the centerline of a county road, running West. Corner has been in existence for over 40 years and checks well with other GLO corners East/West/North/South.

I accept the steel rail as the best available evidence for restoring the corner position.

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced the steel rail with a 2" diameter by 30" long split base aluminum pipe monument with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R34W, S-29, S-30, S-31, S-32, 1997, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Elm	6"	S 52° E	42.94 feet
Black Cherry	8" dbl	S 32° E	26.15 feet
Rebar	5/8"x30"	N 78° W	20.91 feet
Rebar	5/8"x30"	N 59° E	29.24 feet
Steel sign post		S 14° E	0.90 feet

98-22

Signed by Gary L. Pisoni Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971



1.7 P 239