

MAR 9 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>34W</u>	<u>C-13</u> ✓
	T <u>42N</u> R <u>34W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:26

L.C. Regado: L. 8, P. 94

Richard L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner to Sections 31 and 32, T43N, R34W
Section Corner to Sections 6 and 5, T42N, R34W

I, Gary L. Pisoni, in a field survey on Sept. 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 8, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner; Maple Wood Post
Original Bearing Trees:

Sugar	8"	N 16° E	13 lks (8.58 feet)
Lynn	9"	N 52° W	42 lks (27.72 feet)

On October 13, 1851, Guy Carleton, U.S. Deputy Surveyor, made two (2) new bearing trees:
Yellow Birch 10" S 25° E 20 lks (13.20 feet)
Sugar 9" S 75° W 35 lks (23.10 feet)

PEER GROUP APPROVED

Donny L. Pisoni 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a bent iron bar marking the corner position. Iron bar lines up with the East edge of a farm field running North and in line with the centerline of a road running West. Iron bar is consistent with GLO distances East and West. I accept the iron bar as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I replaced the bent iron bar with a 5/8" diameter by 30" long rebar with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R34W, S-31, S-32, S-6, S-5, T42N, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Basswood Clump	8"	S 47° W	35.40 feet
Basswood Clump	6"	N 61° W	41.61 feet
Cherry (dbl)	14"	N 20° E	25.59 feet
Steel sign post		East	0.95 feet

99-94
Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28, 1971
REVISOR MAY 14, 1975
REVISOR JAN, 1983
REVISOR OCT., 1995

