

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 97 DEC 23 PM 1:30
 L.C. Records L.7 P. 161
Gilbert L. Pisoni
 REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u> T <u>43N</u> R <u>34W</u> T _____ R _____ T _____ R _____	E-13 <u>E-1</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner Sections 32, 33, T44N, R34W
 Sections 4, 5, T43N, R34W

I, Gary L. Pisoni, in a field survey on November 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by William A. Burt, U.S. Deputy Surveyor.
 Original Corner: Maple Post
 Original Bearing Trees:

Yellow Birch	18"	N 19° E	42 lks (27.72 feet)
Sugar	10"	N 08° W	22 lks (14.52 feet)

On 7/29/77, Arthur O. Enger RLS, DNR, found an old scribed white painted cedar post marking corner position. Position checks with other corners in the area. Set a 1" x 36" iron pipe with a 3 3/4" dia. aluminum cap stamped as follows: DNR, T44-43N, R34W, S32, S33, S5, S4, RLS 13581, Recorded in Land Corner Certificate L. 1, Page 542 on 9/12/77.

1977 Bearing Trees

Sugar Maple	5"	N 41° W	14.2 feet
Sugar Maple	4"	S 87° W	5.1 feet

PEER GROUP APPROVED
Gary L. Pisoni 12-19-97
 IRON COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found..

On November 28, 1997, found monument as set by Arthur O. Enger RLS in 1977 along with the following bearing trees:

Sugar Maple	5"	N 53° W	14.32 feet
Sugar Maple	6"	S 76° W	5.13 feet

[accept the DNR monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (measurement taken to a nail in side of tree)

Utility Pole	No. # on pole	N 87° E	30.43 feet
Balsam	8"	S 32° E	32.75 feet
Steel sign post	6"	S 32° W	0.90 feet

97-8a
 Signed by *Gary L. Pisoni* Date December 16, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT., 1995

