

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 34W

E-7

2. Property Controlling in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 16, 17, 20, 21, T43N, R34W

I, Gary L. Pisoni, in a field survey on September 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by G.H. Carleton, U.S Deputy Surveyor in 1851.

Original corner: Wood Post

Original bearing trees:

Yellow Birch	14"	S 40° E	43 links (28.38 feet)
Sugar	16"	N 28° W	49 links (32.34 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 1/2" x 30" iron pin. Corner position has been used and accepted as the corner locally for many years. Corner position checks within reason to GLO distance from other GLO corners located East/West/North/South. Set an aluminum pipe monument over the top of iron pin as described below. Monument is 3" above ground surface. This corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representative's Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A.P. 11-30-94

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R34W, S-17, S-16, S-20, S-21, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	9"	N 78° W	31.55 feet
Sugar Maple	7"	N 52° E	42.43 feet
Sugar Maple	13"	S 78° E	8.12 feet
Sugar Maple	5"	S 51° W	8.98 feet
Steel Sign Post		N 60° W	1.20 feet

Signed by Gary L. Pisoni

Date 1-9-95

Surveyor's Michigan License No. 77457

REGISTER'S OFFICE)
IRON COUNTY, MICH.) ..SS
RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P. M. AND RECORDED IN LIBER
6 OF L.C. RECORDS
ON PAGE 359
Mark Jones
DEPUTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PEER GROUP APPROVED
Gary L. Pisoni
COUNTY REPRESENTATIVE

