

MAR 9 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Iron (County), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, etc.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:26

L.C. Records: L. 8, P. 96

Signature of County Representative

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner to Sections 32 and 33, T43N, R34W
Section Corner to Sections 5 and 4, T42N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, showing corner locations with dots at specific intersections.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

See Sketch on D-1 or F-1

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 8, 1846 by William A. Burt, U.S. Deputy Surveyor. Original Corner; Aspen Wood Post

Original Bearing Trees: Aspen 12" N 87 1/2° E 6.65 chs (438.90 feet) Aspen 12" N 86° 15' W 6.95 chs (458.70 feet)

On October 10, 1851, Guy H. Carleton, U.S. Deputy Surveyor made the following new bearing tree: Yellow Birch 10" S 15° E 27.00 chs (1782.00 feet)

PEER GROUP APPROVED

Iron Gary L. Pisoni 12-21-99 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Restored the corner position by single proportionate measurement and on line between the Northwest corner of Section 5 and the Northeast corner of Section 4, T42N, R34W.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3/4" diameter aluminum rod monument, 3 feet long and 2" above ground surface with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R34W, S-32, S-33, S-5, S-4, T42N, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Steel sign post East 0.9 feet
Steel sign post South 0.9 feet
Steel sign post West 0.8 feet

99-96

Signed by Gary L. Pisoni

Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971

27457 REVISED MAY 12, 1975 REVISED JAN., 1983 REVISED OCT., 1995

