

RF

MAR 9 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 34W

F-13 ✓

T 42N R 34W

F-1

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:26

L.C. Records: L.S.P. 99

Gilbert Selie
REGISTERED SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Section 33, T43N, R34W
Quarter Corner to Section 4, T42N, R34W

I, Gary L. Pisoni, in a field survey on Oct. 23, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

N 89° 58' 16" E 10542.53

31 | 32 N 89° 58' 16" E N 89° 58' 16" E 32 | 33 S 89° 48' 08" W N 89° 51' 36" W 33 | 34
6 | 5 2635.63 114 2635.63 5 | 4 2635.66 114 2635.64 4 | 3

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 8, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner; Ironwood Post
Original Bearing Trees:

Yellow Birch 7" N 32° E 25 lks (16.50 feet)
Sugar 5" N 53° W 27 lks (17.82 feet)

PEER GROUP APPROVED

Iron Gary L. Pisoni 12-31-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Restored the corner position on an old fenceline and midway between the Northeast and Northwest Section corners of Section 4, T42N, R34W. Corner is located 46 feet East of a fenceline which runs North and South.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 5/8" diameter by 30" long rebar with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R34W, 1/4, S-33, S-4, T42N, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple 12" N 75° E 39.17 feet
Sugar Maple 11" S 39° E 34.02 feet
Sugar Maple 12" S 59° W 14.84 feet
Steel sign post N 58° E 0.7 feet
Roof Bolt S 69° 51' 53" W 46.56 feet

99-97

Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT., 1995

