

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Iron), Located in (T 43N R 34W), Corner Code # (G-6), and survey types (Public Land Survey, Property Controlling, Miscellaneous).

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:33

L.C. Records: L. 8, P. 133

Signature of Gary L. Pisoni

Register of Deeds Stamp & File Number

4. Lot No. ... Recorded Plat ...
5. Private Claims ...

Quarter corner to Sections 15 and 16, T43N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of row 6 and column G.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 2, 1851 by Guy H. Carleton, U.S. Deputy Surveyor. Original Corner; Quarter Post Original Bearing Trees:

Table listing bearing trees: Tamarack 8" S 50° W 35 lks (23.10 feet), Tamarack 8" N 30° E 30 lks (19.80 feet)

PEER GROUP APPROVED Gary L. Pisoni 12-31-99 COUNTY REPRESENTATIVE

On July 8, 1982, Gary L. Pisoni RLS, restored the corner position from the above original bearing trees and set a 1" diameter x 6' long aluminum rod monument with a 2 1/2" diameter aluminum cap stamped as follows: T43N, R34W, 1/4, S-15, S-16, 1983, RLS 27457 and recorded in Liber 5, Page 46 of L.C. records.

1983 Bearing Trees

Table listing 1983 bearing trees: Tamarack 6" N 20° E 7.78 feet, Tamarack 9" S 39° W 23.88 feet, Tamarack 8" N 39° W 13.19 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/5/99, found monument as described above and the following bearing trees:

Table listing bearing trees found: Tamarack 8" N 20° E 7.75 feet, Tamarack 12" S 35° W 23.88 feet, Tamarack 11" N 37° W 13.16 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Table listing new bearing tree: Tamarack 10" S 11° E 26.76 feet, Steel sign post North 0.55 feet

99-133 Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

