

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Iron (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 30 AM 10:14

L.C. Records: L. 8, P. 29

Handwritten signature and name of County Representative.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Section Corner to Sections 35 and 36, T44N, R34W
Section Corner to Sections 2 and 1, T43N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical data points for survey locations.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor. Original Corner; Sugar Post Original Bearing Trees:

Table listing bearing trees: Sugar 10" N 59 1/2° E 46 lks (30.36 feet), Lynn 18" N 32° W 17 lks (11.22 feet)

On August 30, 1851, Guy H. Carleton, U.S. Deputy Surveyor established the following bearing trees:

Table listing bearing trees: Sugar 12" S 75° E 48 lks (31.68 feet), Sugar 9" S 65° W 28 lks (18.48 feet)

On 8/16/79, Arthur O. Enger, RLS, DNR, restored the corner position by single proportionate measurement along the town line and set a 1" diameter by 36" long iron pipe with a 3 3/4" aluminum cap stamped as follows: T44N, R34W, S-35, S-36, S-2, S-1, T43N, 8/16/79, RLS 13581 recorded in Liber 2b, Page 9 of LC records.

1979 Bearing Trees:

Table listing bearing trees: Sugar Maple 15" N 03° W 18.4 feet, Sugar Maple 12" S 72° E 14.8 feet, Sugar Maple 13" S 61° W 24.3 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/12/99, found the monument as described above and the following bearing trees:

Table listing bearing trees: Sugar Maple 13" S 70° E 15.10 feet, Sugar Maple 15" S 61° W 24.76 feet

Monument is 16" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Table listing new bearing trees: Sugar Maple 8" N 41° W 14.58 feet, Sugar Maple 7" N 40° E 49.33 feet, Steel sign post West 1.2 feet

99-29 Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 No. 27457 REVISIONS: MAY 14, 1975; REVISED JAN., 1983; REVISED OCT., 1995

PEER GROUP APPROVED Ron Pisoni 12-21-99 COUNTY REPRESENTATIVE

