

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>34W</u>	<u>L-13</u>
	T <u>43N</u> R <u>34W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:14
L.C. Records: L. 8, P. 30
Gary L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Section 36, T44N, R34W
Quarter Corner to Section 1, T43N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3			2	1
3													
4	7			8		9			10			11	12
5													
6	18			17		16			15			14	13
7													
8	19			20		21			22			23	24
9													
10	30			29		28			27			26	25
11													
12	31			32		33			34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor.
Original Corner; Cedar Post
Original Bearing Trees:

Fir	7"	N 82° E	48 lks (31.68 feet)
Yellow Birch	14"	N 13° W	17 lks (11.22 feet)

PEER GROUP APPROVED
Iron Inv. Pisoni 12-21-99
COUNTY REPRESENTATIVE

On 8/20/79, Arthur O. Enger, RLS, DNR, restored the corner position by single proportionate measurement along the Town line and set a 1" diameter by 36" long iron pipe with a 3 3/4" aluminum cap stamped as follows: T44N, R34W, 1/4, S-36, S-1, T43N, 8/20/79, RLS 13581, recorded in Liber 2b, Page 9 of LC records.
1979 Bearing Trees:

Red Maple (dbl)	7"	S 71° E	53.7 feet
Red Maple	6"	N 51 1/2° E	28.2 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/12/99, found the monument as described above, no evidence of bearing trees found. Monument located in a tag alder swamp. Monument is 8" above ground surface.
Found a Wood Post 6" dia. North 0.8 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees; (All measurements taken to a nail in side of tree)

Balsam	10"	N 23° E	14.71 feet
Cherry	3"	S 26° E	9.58 feet
W. Birch	3"	S 60° W	8.95 feet
Balsam	3"	N 70° W	24.55 feet
Steel sign post		East	0.75 feet

99-30
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

