

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 43N R 34W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD**

98 DEC 28 AM 11:11  
L.C. Records: L. 7, P. 237

*Gilbert Stiehl*  
REGISTERED DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 24 and 25, T43N, R34W

I, Gary L. Pisoni, in a field survey on October 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.  
Original Corner; Wood Post  
Original Bearing Trees:

Hemlock	12"	N 26°W	49 lks (32.34 feet)
Yellow Birch	28"	S 29°E	60 lks (39.60 feet)

**PEER GROUP APPROVED**  
Iron A. Pisoni 11-24-98  
**COUNTY REPRESENTATIVE**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original B.T.s found.

Corner located in the center of a gas pipeline. Corner position was previously marked by an iron bar for over 20 years, but was destroyed during pipeline construction in 1993. I reset the corner position with a 5/8" diameter by 30" long rebar in the center of the pipeline and 6" below ground surface. Corner is on line and midway between the SW and SE Section corners of Section 24.

Corner record research on file with county representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position, set a 3" diameter aluminum cap over the top of the existing rebar pin and stamped as follows:  
Iron County Remonumentation, T43N, R34W, 1/4, S-24, S-25, 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Popple	12"	N 15° E	35.18 feet
Popple	8"	N 70° E	53.20 feet
Rebar	5/8"x30"	S 16° E	56.26 feet
Scotch Pine	14"	S 32° W	34.03 feet
Steel sign post		South	3.83 feet

98-20  
Signed by Gary L. Pisoni Date 12-21-98  
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

**STATE OF MICHIGAN**  
GARY L. PISONI  
PISONI  
LAND  
SURVEYOR  
No. 27457  
REGISTERED LAND SURVEYOR

REVISED MAY 14, 1975  
REVISED JAN. 1983  
REVISED OCT. 1995

1.7 P. 237