

**SURVEY & REMONUMENTATION**

**JAN 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

97 DEC 23 PH 1:31  
 L.C. Records L.P. 169  
*Gilbert Stebbins*  
 REGISTER OF DEEDS

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>33W</u>	<u>A-7</u>
	T <u>43N</u> R <u>34W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner 13 T43N R34W 18 T43N R33W  
 24 19

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Gary L. Pisoni, in a field survey on March 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original corner established by Austin Burt, U.S. Deputy Surveyor on September 11, 1846.  
 Original corner: Sugar Post  
 Original bearing trees:  
 Sugar Maple 16" S 29° E 37 Links (24.42 feet)  
 Hemlock 32" N 68° W 13 Links ( 8.58 feet)  
 On September 9, 1851, Guy H. Carleton, U.S. Deputy Surveyor, established the following bearing trees:  
 Hemlock 24" S 33° W 12 Links ( 7.92 feet)  
 Sugar Maple 14" N 14° E 14 Links ( 9.24 feet)  
 In November, 1972, Arthur O. Enger, R.L.S. for M.D.N.R. set a 5" x 36" re-inforced concrete cylinder with 4" aluminum cap from a found 1 1/4" x 36" iron pipe at corner position.  
 Pipe believed to be set by E. Davison, former County Road Engineer. Recorded in Land Corner Certificate L.1, P.291, 292 on 7/31/74.  
 Enger's 1972 bearing trees:  
 White Birch 12" N 73° E 10.31 feet  
 Sugar Maple 7" S 56° E 21.00 feet  
 Sugar Maple 7" N 87° W 42.81 feet

PEER GROUP APPROVED  
*Gary L. Pisoni 12-19-97*  
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No original corner evidence found. Found said monument with broken concrete top and broken aluminum cap. Accepted monument as the best available evidence for restoring corner position and set pipe monument as described below.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with 3" cast aluminum cap stamped to read: T43N, R34W, R33W, S-13, S-18, S-24, S-19, 1997, RLS - 27457 from which I established the following new blazed and scribed bearing trees:  
 (All measurements taken to a nail in side of tree)  
 Sugar Maple 6" N 10° E 8.88 feet  
 White Birch (Existing) 18" N 75° E 10.57 feet  
 Basswood 12" S 52° E 13.63 feet  
 Sugar Maple 7" S 63° W 31.87 feet  
 Steel Sign Post 6' South 1.00 feet

97-16a  
 Signed by *Gary L. Pisoni*

Date December 16, 1997

Surveyor's Michigan License No. 27457

