

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>A-8</u> ✓
	T <u>43N</u> R <u>36W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
99 DEC 30 AM 10:08
L.C. Records: L. 8, P. 3
[Signature]
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Section 19, T43N, R35W and
Section 24, T43N, R36W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 13, 1846 by John Burt, U.S. Deputy Surveyor. PEER GROUP APPROVED
Original Corner; Yellow Birch Post
Original Bearing Trees: *Iron County Remonumentation 8-24-99*
Yellow Birch 8" S 70°E 12 lks (7.92 feet) COUNTY REPRESENTATIVE
Yellow Birch 6" N 87°W 13 lks (8.58 feet)

On 10-27-67, Donald Lappala, Cadastral Surveyor, found a 3" X 3" X 56" cedar post at record bearing and distance from the two original bearing trees. Set a 2" inside diameter by 2 foot long concrete filled iron pipe with a 3" circular bronze tablet stamped for corner.

1967 Bearing Trees:
Sugar Maple 7" S 78°E 12.3 feet
Sugar Maple 3" S 05°W 24.5 feet
Sugar Maple 7" S 55°W 4.1 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.
On 12-12-98 Found existing brass cap lying on its side, on 3/2/99 reset the corner position with an aluminum pipe monument from the existing bearing trees:
Sugar Maple 13" S 76°E 12.14 feet
Sugar Maple 7" S 06°W 24.47 feet
Sugar Maple 12" S 54°W 4.18 feet
Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described corner position, I set a 2" diameter by 18" long split base aluminum pipe monument, with a 3" aluminum cap stamped as follows: Iron County Remonumentation, T43N, R36W, R35W, 1/4, S-24, S-19, 1999, RLS 27457, from which I blazed and scribed the following new bearing tree: (All measurements taken to 1" side of tree)
Hemlock 18" N 48°W 17.23 feet
Steel sign post S 10°E 5.34 feet

99-03
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

