

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Iron), Located In, Corner Code #, and survey details (Public Land Survey, Property Controlling, etc.)

IRON COUNTY MICHIGAN RECEIVED FOR RECORD 99 DEC 30 AM 10:14 L.C. Records: L. 8, P. 34 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Quarter Corner to Section 31, T43N, R35W
Quarter Corner to Section 36, T43N, R36W

I, Gary L. Pisoni, in a field survey on Nov. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13 for recording corner points.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by John Burt, U.S. Deputy Surveyor
Original Corner; Ironwood Post
Original Bearing Trees: Sugar Maple 5" S 32° W 13 lks (8.58 feet)
Sugar Maple 9" N 27° E 31 lks (20.46 feet)
On 11/3/65, Donald D. Lappala, RLS USFS, restored the corner position from the stump of one of the original bearing trees with GLO blaze, set a 2" diameter by 5' long galvanized iron pipe with a 3" diameter brass cap stamped as follows: T43N, R36W, R35W, 1/4, S-36, S-31, 1965, RLS 12585, recorded in Liber 2, Page 25 of LC records.
1965 Bearing Trees: Sugar Maple 10" N 82° W 20.5 feet
Sugar Maple 7" N 81° E 7.2 feet
Sugar Maple 7" N 47° W 17.3 feet

PEER GROUP APPROVED
Iron County Rep. 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/16/99, found the monument as described above and the following bearing trees:
Sugar Maple 15" N 82° W 20.28 feet
Sugar Maple 12" N 81° E 7.19 feet
Sugar Maple 12" S 48° W 17.34 feet
Wood sign post S 78° W 4.8 feet
Monument is 12" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing tree: (All measurements taken to a nail in side of tree)

Sugar Maple 13" N 02° W 60.18 feet
Steel sign post N 70° E 1.5 feet

99-34 Signed by Gary L. Pisoni Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
No. 27457
REVISOR MAY 14, 1975
REVISOR JAN., 1983
REVISOR OCT., 1995

