

MAR 09 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>A-13</u> ✓
	T <u>43N</u> R <u>36W</u>	<u>M-13</u>
	T <u>42N</u> R <u>35W</u>	<u>A-1</u>
	T <u>42N</u> R <u>36W</u>	<u>M-1</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:09

L.C. Records: L.S., P. 2
Gibson
REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Section 31, T43N, R35W, Section 36, T43N, R36W
Section Corner Section 6, T42N, R35W, Section 1, T42N, R36W

I, Gary L. Pisoni, in a field survey on Dec. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 10, 1846 by John Burt, U.S. Deputy Surveyor.
Original Corner; Sugar Post
Original Bearing Trees:

Sugar	14"	N 16°E	35 lks (23.10 feet)
Yellow Birch	18"	S 46°W	34 lks (22.44 feet)

On 11-02-65, Donald Lappala, Cadastral Surveyor, Restored the corner position from the stump remains of the two original Bearing trees at record bearing and distance, set a 2" diameter by 5' long iron pipe which a 3" brass cap stamped as follows: T43N, R36W, R35W, S-36, S-31, S-1, S-6, T42N, 1965, RLS 12585. Distance from corner West and North to lake in accordance with original field notes.

1965 Bearing Trees:

Sugar Maple	6"	N 60°W	13.5 feet
Sugar Maple	7"	N 08°E	43.4 feet
Elm	10"	S 64°W	15.5 feet

PEER GROUP APPROVED
Iron Range Room 8-24-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. On 12-12-98 found monument as set by Donald Lappala R.L.S. in 1965 and the following bearing trees:

Sugar Maple	11"	N 64°W	13.40 feet
Sugar Maple	9"	N 05°E	43.29 feet
Wood Sign Post		West	2.20 feet

Corner record research on file with county representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	10"	S 03°E	32.74 feet
Sugar Maple	9"	S 50°W	6.00 feet
Steel Sign Post		S 28°W	0.90 feet

99-02
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 24, 1975
REVISED JAN. 1983
REVISED OCT., 1995

