

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>C-11</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:19

L.C. Record: L. 7, P. 281

Gilbert Stiles

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 29, 30, 31 and 32, T43N, R35W

I, Gary L. Pisoni, in a field survey on Nov. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in August, 1851 by Harvey Mellen, Deputy Surveyor.
Original Corner: Wood Post
Original Bearing Trees:

Spruce	14"	S 73° W	23 lks (15.18 feet)
Cedar	16"	N 69° W	35 lks (23.10 feet)

On 9/25/70, Donald D. Lappala, RLS U.S.F.S., restored the corner position from a found 3/4" diameter iron pin located in the centerline of Ottawa Lake Road which runs East and West and the centerline of a County Road which runs South. At the corner position, he set a reference monument being a 2" diameter by 5' long galvanized iron pipe with a 3" brass cap stamped as follows: T43N, R35W, R.M., S-29, S-30, S-31, S-32, South 30.09 feet, RLS 12585, 1970, 14" above ground surface recorded in L.C. Certificate Liber 3, Page 14 on 7/17/72.

1970 Bearing Trees:

Cedar	4"	N 18° W	64.0 feet
Cedar	6"	N 02° W	73.1 feet
WI/MI Power Pole #3265		N 49° E	50.8 feet

PEER GROUP APPROVED
Iron Pisoni 12-18-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found monument as described above and the following reference monument:
R.M. 2" x 5' brass capped iron pipe North 30.18 feet

I accept the above monument as the best available evidence for restoring the corner position.
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


From the above described corner, I blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Utility Pole #75-0517		N 49° E	49.57 feet
Cedar	8"	S 53° E	86.60 feet
Tamarack	8"	S 58° W	87.10 feet
Steel sign post		North	31.15 feet

98-116
Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 12-21-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 281