

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:22

L.C. Records: L. 7, P. 297

[Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sections 31, and 32, T43N, R35W

I, Gary L. Pisoni, in a field survey on Nov. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Harvey Mellen, U.S. Deputy Surveyor.
Original Corner; Wood Post
Original Bearing Trees:

Yellow Birch	15"	N 15° W	10 links (6.60 feet)
Elm	12"	S 22° W	28 links (18.48 feet)

On 10/9/70, Donald D. Lappala, RLS U.S.F.S., restored the corner position in the centerline of a North/South County Road and on a fence line running East and West.
At the corner position, he set a 1" diameter iron rod, 4" below the roadbed surface with a reference monument being a 2" diameter by 5' long galvanized iron pipe with a 3" brass cap stamped as follows: T43N, R35W, R.M., 1/4, S-31, S-32, East 25.70 feet, RLS 12585, 1970, 18" above ground surface recorded in L.C. Certificate Liber 3, Page 15 on 7/17/72.

1970 Bearing Trees:

Elm	6"	N 80° W	32.5 feet
Elm	4"	N 28° W	67.1 feet
Elm	10"	S 37° W	61.1 feet

PROCESSED AND APPROVED
Iron H. Pisoni 12-18-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found monument as described above and the following reference object:
R.M. 2" x 5' brass capped iron pipe West 25.58 feet

I accept the above monument as the best available evidence for restoring the corner position.
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	7"	S 53° E	40.40 feet
Sugar Maple	7"	S 40° W	44.14 feet
Sugar Maple	7"	N 30° W	62.33 feet
Steel sign post		West	26.25 feet

98-145
Signed by Gary L. Pisoni Date 12-21-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 297