

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY MICHIGAN RECEIVED FOR RECORD

93 DEC 29 PM 2:19

L.C. RECORDS L.C. P. 278

Register of Deeds Stamp & File Number

For corners in

Table with columns: Iron (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Quarter Corner 4-9 T43N R35W

I, Gary L. Pisoni, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Harvey Mellen, U.S. Deputy Surveyor in 1851.

Original corner: Wood Post

Original bearing trees:

Table listing bearing trees: Sugar Maple (10" N 03° W, 20 links (13.20 feet)), Spruce (16" S 43° W, 17 links (11.22 feet)).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 3/4" X 32" iron pin. Corner position has been used and accepted locally, for many years. Set an aluminum pipe monument and placed iron pin next to corner. Monument located on North edge of pipe line. Monument is 3" above ground surface.

This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, 1/4, S-4, S-9, 1993, R.L.S. 27457; from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Table listing new bearing trees: Red Pine (6" N 25° E, 44.82 feet), Red Maple (8" N 89° E, 24.81 feet), Red Maple (dbl) (9" S 46° W, 71.07 feet), Spruce (7" N 44° W, 40.52 feet), Steel sign post (South, 0.97 feet).



Signed by Gary L. Pisoni

Date 12-28-93

Surveyor's Michigan License No. 27457