

FEB 22 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R 35W

G-1

T 43N R 35W

G-13

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE )  
IRON COUNTY, MICH. ) SS  
RECEIVED FOR RECORD THE 21<sup>ST</sup> DAY OF  
FEBRUARY AD. 19 95 AT  
2:45 O'CLOCK P. M., AND RECORDED IN LIBER  
6 OF L.C. RECORDS  
ON PAGE 360  
Maui S. Davis  
DEPUTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

Section Corner 33, 34, 4, 3, T43N, R35W

T42N

I, Gary L. Pisoni, in a field survey on September 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor in 1846.

Original corner: Hemlock Post

Original bearing trees:

Sugar 14" N 37°E 33 links (21.78 feet)  
Sugar 6" N 55°W 42 links (27.72 feet)

Original corner recovered by Harvey Mellen, U.S. Deputy Surveyor in 1851.

Original bearing trees:

Yellow Birch 24" S 47°W 19 links (12.54 feet)  
Hemlock 10" S 63°E 38 links (25.08 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 1" x 30" drill rod and located in the centerline of a North/South county road and in the centerline of a county road running East. Corner position has been used and accepted as the corner locally for many years. Set an aluminum pipe monument over the top of the drill rod as described below. Monument is flush with ground surface.

This corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representatives Office.

PEER GROUP APPROVED  
Iron County Rep. Office  
COUNTY REPRESENTATIVE  
A.P. 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, S-33, S-34, S-4, S-3, T42N, 1994, RLS- 37457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Utility Pole #M6-2-18 N 56°E 42.48 feet  
Rebar 5/8" x 30" S 49°E 76.85 feet  
Yellow Birch 13" S 33°W 57.74 feet  
Rebar 5/8" x 30" N 31°W 28.35 feet  
Steel Sign Post N 47°W 1.12 feet

Signed by Gary L. Pisoni

Date 1-9-95

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

