FEB 2 2 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Iron (County)

REGISTER'S OFFICE) SS
IRON COUNTY, MICH.)
RECEIVED FOR RECORD THE 21ST DAY OF FEBRUARY A.D. 19 95 AT 2:45 O'CLOCK P M., AND RECORDED IN LIBER 6 OF L.C. RECORDS ON PAGE 355
Mark DeNuis
DEPUTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T 43N R 35W	H-1 ✓
	T 44N R 35W	H-13
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



Quarter Corner 34, 3, T44N, R35W
T43N

I, Gary L. Pisoni, in a field survey on September 13, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S Deputy Surveyor in 1847.
Original corner: Fir Post
Original bearing trees:

Yellow Birch	18"	N 31°E	59 links (38.94 feet)
Yellow Birch	12"	N 42°W	36 links (23.76 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by a 5/8" x 17" rebar, set by Gerald W. Carlson RLS #24589 from a section sub-division of Section 3. Corner set by single proportionate meaurement and on line between the Northwest and Northeast section corners of Section 3. Set an aluminum pipe monument over the top of rebar pin as described below. Monument is 3" above ground surface.

This corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representatives Office.

PEER GROUP APPROVED
Iron Gary L. Pisoni
COUNTY REPRESENTATIVE
N.P. 11-30-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T44N, R35W, 1/4, S-34, S-3, T43N, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Aspen (existing)	7"	S 82°W	44.70 feet
Aspen	8"	S 49°W	64.04 feet
Aspen	8"	S 67°W	65.10 feet
Aspen	6"	N 73°W	45.72 feet
Steel Sign Post		North	1.11 feet

STATE OF MICHIGAN
GARY L. PISONI
LAND SURVEYOR
No. 27457
REGISTERED LAND SURVEYOR

Signed by Gary L. Pisoni Date 1-9-95

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983