

FEB 2 1996

ADMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 42N R 35W

H-1

T 43N R 35W

H-13 ✓

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE)
IRON COUNTY, MICH.) ..SS
RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P.M. AND RECORDED IN LIBER
6 OF L.C. RECORDS
ON PAGE 371
DEPUTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Quarter Corner 34, 3, T43N, R35W
T42N

I, Gary L. Pisoni, in a field survey on October 21, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor in 1846.
Original corner: Ironwood Post
Original bearing trees:

Sugar 14" N 75° E 4 links (2.64 feet)
Sugar 16" N 36° W 36 links (23.76 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by an iron bar and located in the centerline of an East/West county road and a fence line running North. Corner position has been used and accepted as the corner locally for many years. Set an aluminum pipe monument over the top of the iron bar as described below. Monument is 6" below road bed surface.

The corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representative Office.

PEER GROUP APPROVED

Gary L. Pisoni

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: AP. 11-30-94

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, 1/4, S-34, S-3, T42N, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Rebar 5/8" x 30" N 30° W 44.92 feet
Sugar Maple 12" S 22° E 29.42 feet
Sugar Maple 8" S 50° W 58.04 feet
Rebar 5/8" x 30" N 22° E 42.03 feet
Steel Sign Post South 24.75 feet

Signed by Gary L. Pisoni

Date 1-7-95

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1975
REVISED JAN., 1983

LIBER

6 PAGE 371

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

