

**SURVEY &
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:14

L.P. Records: L. 7, P. 253

Gary L. Pisoni

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 14, 15, 22 and 23, T43N, R35W

I, Gary L. Pisoni, in a field survey on November 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in August, 1851 by Harvey Mellen, Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

White Pine	30"	S 09° W	31 lks (20.46 feet)
White Pine	30"	N 51° E	45 lks (29.70 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a plat monument buried 24" below road bed surface marking the Southwest corner of Homer Plat. Set a P.K. nail in asphalt surface directly above the buried Plat monument. I accept the Plat monument as the best available evidence for restoring the corner position.

P.K. nail is 4' West of the centerline of Homer Road.

Corner record research on file with County Representative.

PEER GROUP APPROVED
Gary L. Pisoni 11-24-98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set one (1) reference monument being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R35W, R.M., S-14, S-15, S-22, S-23, S 63° E, 19.20 feet, 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Utility Pole	N 72° W	18.64 feet
R.M. 5/8" x 30" rebar	N 63° W	19.20 feet
Utility Pole #75-1013	N 80° E	28.97 feet
Plat Concrete Monument	East	33.04 feet
Steel sign post	N 63° W	20.06 feet

98-112
Signed by Gary L. Pisoni Date 12-31-98
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JUN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995



L. 7 P. 253