

**SURVEY &
REMONUMENTATION**

JAN 1 2 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 DEC 15 PM 2:22
L.C. Records L.C., P. 421

Gilbert Stetson
REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T43N R35W	I-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 22, 23, 26, 27 T43N R35W

I, Gary L. Pisoni, in a field survey on Oct. 18, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Harvey Mellen, U.S. Deputy Surveyor on August, 1851.
Original corner: Wood Post
Original bearing trees:

Hemlock	30"	S 49°E	40 links (26.40 feet)
Cedar	7"	N 72°W	26 links (17.16 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. At corner position there existed a 1" dia. iron pin located in Homer Road. Iron pin destroyed during road construction in the summer of 1995. Reset corner position from previous witnesses to corner.

PEER GROUP APPROVED

Iron County Peer Group 12-14-95

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Research on file with County Representative.
At the corner position, I set a Railroad Spike 2 feet East of the Centerline of Homer Road and set a Witness Corner on the East right-of-way limit of Homer Road stamped to read: Iron County Remonumentation, T43N, R35W, W.C., S-22, S-23, S-27, S-26, 41.70', N89°37'55"W, 1995, RLS- 27457 from which I established the following new bearing tree and accessories (all measurements taken to a nail in side of tree)

Balsam	10"	S 78°W	48.60 feet
Utility Light Pole		N 45°W	42.79 feet
W.C.	2" x 30" Mon.	S 89°37'55"E	41.70 feet
NW Cor. Rectangular Cast			
Man-hole	1.5' x 3.5'	N 63°E	34.46 feet
Steel Sign Post		East	42.43 feet

Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date _____

