

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

99 DEC 30 AM 10:14

*L.C. Records: L. 8, P. 32*

*Gary L. Pisoni*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner to Sections 26, 27, 34, 35, T43N, R35W

I, Gary L. Pisoni, in a field survey on Nov. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in August, 1851, by Harvey Mellen, U.S Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Sugar	12"	S 45° E	No distance
White Pine	28"	S 51° W	41 lks (27.06 feet)

PEER GROUP APPROVED

*Gary L. Pisoni 12-21-99*

COUNTY REPRESENTATIVE

In 1980, Gary L. Pisoni RLS found a brass capped concrete monument, 10" below roadbed surface marking corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11/16/99, found the above described monument and set a p.k. nail in the blacktop surface of a East/West county road. Monument has been used for many surveys in the surrounding areas and is consistent with GLO distances to the North, East, South and West. I accept the brass capped monument as the best available evidence for restoring the corner position. P.K. nail is 6.1 feet South of centerline.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set one (1) reference monument, being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R35W, R.M., S-26, S-27, S-34, S-35, South, 33.00 feet, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

R.M.	5/8" x 30" rebar	North	33.00 feet
White Spruce	15"	S 41° E	44.30 feet
Concrete elevation marker		S 63° W	39.58 feet
Steel sign post		North	33.40 feet

99-32  
Signed by Gary L. Pisoni

Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

