

**SURVEY &  
REMONUMENTATION**

**JAN 12 1996**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

95 DEC 15 PM 2:22  
LC Records L.G., P. 418

*Gilbert Stebbins*  
REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T44N R35W	K-13
	<u>T43N R35W</u>	<u>K-1</u>
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 35 & 36 T44N R35W  
2 & 1 T43N R35W

I, Gary L. Pisoni, in a field survey on Sept. 14, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by William A. Burt, U.S. Deputy Surveyor in 1847.  
Original corner: Hemlock Post  
Original bearing trees: Sugar 16" N 05°E 25 links (16.50 feet)  
Sugar 8" N 27°W 25 links (16.50 feet)  
Additional BT's established by Harvey Mellen, U.S Deputy Surveyor on 8/7/1851.  
Original bearing trees: Sugar 12" S 75°E 41 links (27.06 feet)  
Sugar 14" S 75°W 48 links (31.68 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original corner evidence found. Found a 3/4" dia. iron pipe marking corner position. GLO distance along section line and to the natural feature ties check good. I accept the iron pipe as the best available evidence for restoring the corner position.

Research on file with County Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T44N, R35W, S-35, S-36, S-2, S-1, T43N, 1995, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	10"	S 75°E	20.12 feet
Sugar Maple	10"	S 23°W	14.36 feet
Sugar Maple	10"	N 30°W	41.36 feet
Sugar Maple	10"	N 10°E	50.10 feet
Steel Sign Post		S 64°W	0.76 feet

Signed by Gary L. Pisoni  
Surveyor's Michigan License No. 27457

Date 11-30-95

PEER GROUP APPROVED

*Gary L. Pisoni 12-14-95*

IRON COUNTY REPRESENTATIVE

