

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>43N</u> R <u>35W</u> | <u>K-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER'S OFFICE) ..SS
 IRON COUNTY, MICH.)
 RECEIVED FOR RECORD THE 21ST DAY OF
FEBRUARY A.D. 19 95 AT
2:45 O'CLOCK P. M. AND RECORDED IN LIBER
6 OF L.C. RECORDS
 ON PAGE 365
Mark [Signature]
 DEPUTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 2, 1, 11, 12, T43N, R35W

I, Gary L. Pisoni, in a field survey on October 18, 19 94
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Harvey Mellen, U.S Deputy Surveyor in 1851.
 Original corner: Wood Post
 Original bearing trees:
 Sugar 18" N 58° W 32 links (21.12 feet)
 Yellow Birch 20" S 26° E 18 links (11.88 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found marked by an iron bar and located in the centerline of a North/South county road and in line with an old fence line running West. Corner position has been used and accepted as the corner locally for many years. Set an aluminum pipe monument over the top of iron bar as described below. Monument is 6" below road bed surface.

This corner is accepted as the best available evidence of the position of the original corner.

County Record Research on file with County Representative office.

PEER GROUP APPROVED
Mark [Signature]
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A.P. 11-30-94

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, S-2, S-1, S-11, S-12, 1994, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail inside of tree)

Red Maple	17"	S 33° W	63.70 feet
Red Pine	12"	N 79° W	55.05 feet
Sugar Maple	8"	N 23° E	55.01 feet
Red Maple	13"	N 60° E	80.44 feet
Steel Sign Post		West	29.56 feet

Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

