

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>35W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:32

L.C. Records: L. 8, P. 129

Gary L. Pisoni

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Sections 25 and 36, T43N, R35W

I, Gary L. Pisoni, in a field survey on Nov. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 8, 1851 by Harvey Mellen, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Lynn	16"	S 79° E	18 lks (11.88 feet)
Cedar	14"	N 9° W	30 lks (19.80 feet)

In 1882, John V. Suydam, Surveyor, set the North quarter corner of Section 36 which is also known as the Northeast Corner of the Plat of the Village of Stambaugh.

In 1926, E.L. Laing, Registered Engineer, set an iron bar at the North quarter corner of Section 36 which is being used as the Northwest corner of the Assessor's Plat No. 2 to the City of Stambaugh.

PEER GROUP APPROVED

Gary L. Pisoni 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found iron bar as described above, located in the centerline of Lincoln Avenue which runs North and South and the centerline of Kofmehl Road.

I accept the iron bar as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set one (1) reference monument, being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R35W, R.M., 1/4, S-25, S-36, N 42° W, 49.02 feet, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree

Maple	18"	N 29° E	53.08 feet
Fire Hydrant - top		S 37° E	42.17 feet
R.M.	5/8"x 30" rebar	S 42° E	49.02 feet
Utility Pole	#100	N 83° W	23.15 feet
Utility Pole	MBT Co.	N 32° W	44.34 feet

99-129

Signed by *Gary L. Pisoni*

Date 12-28-99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

