

REMONUMENTATION

FEB 22 1996

COMMISSION

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

93 DEC 29 PH 2: 22
L.C. RECORDS L. 6 P. 30

Eileen Stiles
REGISTER OF DEEDS

| | | |
|---------------------------------------|-------------------------|---------------|
| Iron (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 43N R 35W | L-13 ✓ |
| | T 42N R 35W | L-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

Quarter Corner 36-1 T43-42N R35W

I, Gary L. Pisoni, in a field survey on December 21, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 5 | 5 | 4 | 3 | 2 | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor on September 10, 1846.
Original corner: Sugar Post
Original bearing trees:
Elm 20" N 48° E 11 links (7.26 feet)
Elm 20" N 66° W 41 links (27.06 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing tree remains. Corner position found
marked by a drill rod with a punch mark inside of monument box. Corner located
in centerline of 19th Street and on the West side of Lincoln Street.
Quarter corner is part of the Assessor's Plat of Dober dating back to the 1930's.

This corner is accepted as the best available evidence of the position of the
original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above corner monument, I established the following new corner references:
(all measurements taken to reference object or to a nail in side of Utility Pole)

| | | | |
|------------------|----------|---------|------------|
| Utility Pole | #18 | N 54° E | 40.39 feet |
| Telephone Pole | 1900MBT | S 13° W | 53.79 feet |
| Top Fire Hydrant | | N 50° W | 43.08 feet |
| Rebar | 5/8"x30" | N 60° E | 47.45 feet |
| Rebar | 5/8"x30" | S 40° W | 47.44 feet |



Signed by Gary L. Pisoni Date 12-28-93

Surveyor's Michigan License No. 27457