

SURVEY & REMONUMENTATION

JAN 12 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

95 DEC 15 PM 2:21

LC Records L.6 P 403

Eileen Stiles
REGISTER OF DEEDS

For corners in **COMMISSION**

Iron _____ Located in: _____ Corner Code # _____
(County)

1. Public Land Survey
 T 43NR 34W A-4
 T 43NR 35W M-4
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Quarter Corner 12 & 7 T43N R35-34W

I, Gary L. Pisoni, in a field survey on Oct. 12, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 11, 1846

Original corner: Cedar Post

Original bearing trees:

Cedar	7"	N 22°E	19 links (12.54 feet)
Cedar	7"	S 88°W	20 links (13.20 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Found a 1" diameter iron pipe located at a fence corner. Iron pipe has been used as Quarter corner and surveys have been tied to this corner. G.L.O. distance along range line checks good. I accepted the iron pipe as the best available evidence found for restoring the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Research on file with County Representative

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T43N, R35W, R34W, 1/4, S-12, S-7, 1995, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Tamarack	16"	S 35°E	10.75 feet
Tamarack	12"	S 81°E	29.06 feet
Steel Sign Post		West	1.73 feet
Steel Sign Post		North	1.37 feet

PEER GROUP APPROVED
Gary L. Pisoni 12-14-95
COUNTY REPRESENTATIVE

Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 11-30-95